

## Funding Partner Information



**NHDES, Coastal Program** 



**NHDES, Aquatic Resource Mitigation Fund** 



**NH State Conservation Committee, Conservation Grant Program** 



NOAA, National Marine Fisheries

## Permits

NH Department of Environmental Services, RSA 482-A, Wetlands Permit: 2015-00887

NH Department of Environmental Services, RSA 485-A:17, Terrain Alteration: General Permit by Rule Env-Wq 1503.03(f)

NH Department of Environmental Services, RSA 483-B, Shoreland Protection: Permit Exemption per RSA 483-B:5-b,IV

NH Department of Environmental Services, Clean Water Act, Section 401 Certification: WQC #2012-404P-002

US Army Corps of Engineers, Clean Water Act, Section 404 Permit: NAE-2014-02631

US Environmental Protection Agency, National Pollutant Discharge Elimination System, General Permit for Discharges from Construction Activities: Permit No. NHR120000

National Historic Preservation Act, Section 106 Memorandum of Agreement: NHDHR R&C #3280

# Great Dam Removal and Exeter River Restoration Exeter, New Hampshire

## **Property Owners**

## **Town of Exeter**

10 Front Street Exeter, NH 03883 Phone: 603-773-6157 · Fax: 603-772-1355

Paul Vlasich, PE Town Engineer



 $\mathbf{\uparrow}$ 

Site Location Map







# Site Plans

<b>Issued for</b>	Con
Date Issued	Mar
Latest Issue	Mar

# Sheet Index

Number	Drawing Title	Latest Issue
C-1	Legend and General Notes	03/23/16
C-2	Existing Conditions Plan	03/23/16
C-3	Existing Conditions Plan	03/23/16
C-4	Staging & Construction Sequencing	03/23/16
C-5	Structure Demolition Plan	03/23/16
C-6	River Channel Grading Plan	03/23/16
C-7	River Channel Cross Sections	03/23/16
C-8	Typical Cross Sections	03/23/16
C-9	Conceptual Intake Designs	03/23/16
C-10	Restoration and Planting Plan	03/23/16
C-11	Details	03/23/16
C-12	Details	03/23/16

## nstruction

# rch 23, 2016

# rch 23, 2016

VHB Project No. 52151.04

		т	1				Abbroviations	N.
		Le	gend				Abbreviations	
Exist.	Prop.		Exist.	Prop.		Genera	al	Description of Work
		PROPERTY LINE	$ \begin{array}{c} & & & \\ & & & & \\ & & & \\ & & & & \\ & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & & & & \\ & $	in the second se		ABAN	ABANDON	1. THE GOALS OF THIS PROJECT ARE TO: REMOVE THE GREAT DAM AND STABILIZE THE RIVER BED IN A WAY THAT PROTECTS THE ADJACENT PROPERTIES WHILE CREATING UPSTREAM PASSAGE FOR DIADROMOUS FISH SPECIES SUCH AS AMERICAN SHAD.
	<b>—</b> — — — —	LIMIT OF WORK RIGHT-OF-WAY/PROPERTY LINE	28702987		RIPRAP	ACR	ACCESSIBLE CURB RAMP	2. THE GREAT DAM IS A CONCRETE DAM WITH AN OGEE STYLE SPILLWAY, A FISH LADDER, A LOW-LEVEL OUTLET, AND A PENSTOCK WITH ITS ASSOCIATED HEADWORKS. THE DAM IS APPROXIMATELY 1.36 FEET LONG BY APPROXIMATELY 1.6 FEET HIGH
		EASEMENT			CONSTRUCTION ENTRANCE	ADDROX	ADDROVIMATE	MEASURED FROM THE TOP OF ITS TALLEST ABUTMENT TO THE STREAMBED AT ITS DOWNSTREAM FACE.
		BUILDING SETBACK	27.35 TC×	27.35 TC×	TOP OF CURB ELEVATION	BIT		3. THE WORK CONSISTS OF COMPLETE REMOVAL OF THE DAM STRUCTURE INCLUDING ALL CONCRETE, METAL, STONE AND WOOD COMPONENTS. THE APPROXIMATE LIMITS AND EXTENT OF DAM REMOVAL ARE DEPICTED ON PLAN SHEETS C-2 AND C-5.
10+00	10+00	PARKING SETBACK	26.85 BC×	26.85 BC×	BOTTOM OF CURB ELEVATION	BS	BOTTOM OF SLOPE	BECAUSE REMOVAL OF THE DAM COULD RESULT IN AN UNSTABLE RIVERBED WITH EXCESSIVE VERTICAL DROPS INHIBITING OR PREVENTING FISH PASSAGE, UP TO APPROXIMATELY 250 LINEAR FEET OF THE RIVER CHANNEL WILL BE RE-GRADED AND STABILIZED WITH DIACED RID DAD. DIACED RID DAD WILL FUNCTION TO STABILIZE THE RIVERDED. DROTECT STREAMBANKS
i		CONSTRUCTION LAYOUT	132.75 ×	132.75 ×	SPOT ELEVATION	BWLL	BROKEN WHITE LANE LINE	AND LIMIT THE VERTICAL DROP ALONG THE RIVERBED. SEE SHEET C-6 FOR PROPOSED LOCATION GRADING AND LIMITS OF PLACED RIP RAP
		ZONING LINE	45.0 TW 38.5 BW	45.0 TW × 38.5 BW ×	TOP & BOTTOM OF WALL ELEVATION	CONC	CONCRETE	4. THE PROJECT WORK ALSO CONSISTS OF THE INSTALLATION OF A DRY-HYDRANT AT THE END OF FRANKLIN STREET,
		TOWN LINE		₩ ■	BORING LOCATION	DYCL	DOUBLE YELLOW CENTER LINE	INSTALLATION OF THE INTAKE PIPE WITHIN THE EXETER RIVER, AND ASSOCIATED CHANNEL WORK.
WTL -		WETLAND LINE	€ <sup>MW</sup>		MONITORING WELL	EL	ELEVATION	5. THE PROJECT WORK ALSO INCLUDES MODIFICATIONS TO THE TOWN OF EXETER RIVER PUMP STATION, LOWERING OF THE INTAKE PIPE WITHIN THE EXETER RIVER, AND ASSOCIATED CHANNEL WORK.
		100-YEAR FLOODPLAIN			PENSTOCK	ELEV	ELEVATION	6. EQUIPMENT SHALL BE STAGED ALONG A FENCED OFF PORTION OF PLEASANT STREET AND ON THE EAST BANK OF THE RIVER IN FOUNDERS PARK WHERE FOUNDMENT WILL ENTER THE STREAM
FLD -		REGULATORY FLOODWAY	UD		LINDERDRAIN	EX	EXISTING	7. REGRADE A PORTION OF THE EAST BANK TO ALLOW EQUIPMENT ACCESS, AND A WOODEN TIMBER BRIDGE (OR APPROVED
OHW -		ORDINARY HIGH WATER	12"D	12″D <b>→</b>	DRAIN	EXIST		EQUAL) WILL NEED TO BE INSTALLED TO PROVIDE ACCESS TO THE DAM. THE CONTRACTOR MAY POTENTIALLY USE THE PROPERTY OWNED BY PETER OLNEY AT 23 WATER STREET TO ACCESS THE RIVER.
SP50 -		TOP OF BANK	6"RD	<u>6″RD</u> →	ROOF DRAIN	FFE	FIRST FLOOR ELEVATION	8. REMOVE ALL CONCRETE FROM THE RIVER, AND HAUL FOR DISPOSAL TO AN APPROVED DISPOSAL FACILITY. COMPLETELY
SP150		150' SHORELINE PROTECTION SETBACK	12_S FM	1 <u>2_5</u> FM	SEWER	FLD	REGULATORY FLOODWAY	REMOVE THE TIMBER ACCESS BRIDGE (OR APPROVED EQUAL) AND HAUL FOR DISPOSAL TO AN APPROVED DISPOSAL FACILITY.
		250' SHORELINE PROTECTION SETBACK	ОНЖ	онw	FORCE MAIN	GRAN	GRANITE	DEFINED AS AN AREA SUBJECT TO INUNDATION BY THE 1-PERCENT-ANNUAL-CHANCE (100-YEAR) FLOOD EVENT DETERMINED BY DETAILED METHODS, ADDITIONALLY, MUCH OF THE WORK IS LOCATED WITHIN A REGULATORY FLOODWAY AS DETERMINED
			6"W	6"W	WATER	GTD	GRADE TO DRAIN	BY FEMA. A REGULATORY FLOODWAY MEANS THE CHANNEL OF A RIVER OR WATERCOURSE AND THE ADJACENT LAND AREAS THAT MUST BE RESERVED IN ORDER TO DISCHARGE THE BASE FLOOD WITHOUT CUMULATIVELY INCREASING THE WATER
		GRAVEL ROAD	4"FP		FIRE PROTECTION	LA	LANDSCAPE AREA	SURFACE ELEVATION MORE THAN A DESIGNATED HEIGHT.
<u>EOP</u>	— — —	EDGE OF PAVEMENT	-11-	2"DW	DOMESTIC WATER	MAX	MAXIMUM	$\frac{\text{General}}{1}$
BC	BC	BITUMINOUS CLIPP	——————————————————————————————————————	——————————————————————————————————————	GAS	MIN		2. ENSURE SITE SECURITY AND JOB SAFETY. CONSTRUCTION ACTIVITIES SHALL BE IN ACCORDANCE WITH OSHA STANDARDS AND
CC	CC	CONCRETE CURB	STM	STM	STEAM	NIC	NOT IN CONTRACT	LOCAL REQUIREMENTS.
	CG	CURB AND GUTTER	T	T	TELEPHONE	ОНМ	ORDINARY HIGH WATER	<ol> <li>APPLY FOUR (4) INCHES OF LOAM AND SEED (UNLESS OTHERWISE NOTED) TO ANY UPLAND AREAS DISTURBED DURING CONSTRUCTION AND NOT RESTORED WITH IMPERVIOUS SURFACES (PAVEMENTS, WALKS, ETC.)</li> </ol>
CC	ECC	EXTRUDED CONCRETE CURB	——FA	FA	FIRE ALARM	PERF	PERFORATED	4. PERFORM ALL WORK IN STRICT COMPLIANCE WITH NH WETLANDS PERMIT, US ARMY CORPS OF ENGINEERS PERMIT, AND ALL
CC	<u> </u>	MONOLITHIC CONCRETE CURB	CAIV		CABLE TV	PROP	PROPOSED	AVAILABLE ON SITE AT ALL TIMES.
SGE	SGE	SLOPED GRAN. EDGING			CATCH BASIN	REM	REMOVE	5. UPON AWARD OF CONTRACT, MAKE NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN NECESSARY PERMITS, PAY FEES, AND POST BONDS ASSOCIATED WITH THE WORK INDICATED ON THE DRAWINGS, IN THE SPECIFICATIONS,
VGC	VGC	VERT. GRAN. CURB			DOUBLE CATCH BASIN	RET	RETAIN	AND IN THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL NOT CLOSE OR OBSTRUCT ROADWAYS, SIDEWALKS, AND FIRE HYDRANTS, WITHOUT APPROPRIATE PERMITS.
		LIMIT OF CURB TYPE	D	D	DRAIN MANHOLE	R&D	REMOVE AND DISPOSE	6. RESTORE AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS TO THEIR ORIGINAL
			=TD=		TRENCH DRAIN	R&R	REMOVE AND RESET	7 IN THE EVENT THAT SUSPECTED CONTAMINATED SOIL GROUNDWATER OR OTHER MEDIA ARE ENCOUNTERED DURING
7	L L	BUILDING BUILDING ENTRANCE	L CO	<b>E</b> C0	PLUG OR CAP	SP50	SHORELINE PROTECTION, 50'	EXCAVATION AND CONSTRUCTION ACTIVITIES BASED ON VISUAL, OLFACTORY, OR OTHER EVIDENCE, STOP WORK IN THE VICINITY OF THE SUSPECT MATERIAL TO AVOID FURTHER SPREADING OF THE MATERIAL, AND NOTIFY THE ENGINEER
	]< ]	LOADING DOCK	•	•	CLEANOUT	SP150	SHORELINE PROTECTION, 150	IMMEDIATELY SO THAT THE APPROPRIATE TESTING AND SUBSEQUENT ACTION CAN BE TAKEN.
٠	•	BOLLARD			HEADWALL	SWEL	SOLID WHITE LANE LINE	8. PREVENT DUST, SEDIMENT, AND DEBRIS FROM EXITING THE SITE AND SHALL BE RESPONSIBLE FOR CLEANUP, REPAIRS AND CORRECTIVE ACTION IF SUCH OCCURS.
D	D	DUMPSTER PAD	(B)	ß	SEWER MANHOLE	ТОВ	TOP OF BANK	9. DAMAGE RESULTING FROM CONSTRUCTION LOADS SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR OWN EXPENSE.
		DOUBLE SIGN	۳	۳	CURB STOP & BOX	TS	TOP OF SLOPE	10. CONTROL STORMWATER RUNOFF DURING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF SITE AREAS, AND SREPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO THE TOWN OF EXETER OR ADJACENT PROPERTY OWNERS. DAMAGE RESULTING
			TSV	TSV	WATER VALVE & BOX	TYP	TYPICAL	FROM STORMWATER RUNOFF SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR OWN EXPENSE.
T	<u>T T</u>	STEEL GUARDRAIL			SIAMESE CONNECTION	WSE	WATER SURFACE ELEVATION	11. FOR PURPOSES OF THIS PLAN SET AND CONSTRUCTION SPECIFICATIONS, THE TERMS ENGINEER AND MONITOR SHALL BE SYNONYMOUS AND SHALL MEAN THE INDIVIDUAL OR FIRM RETAINED BY TOWN OF EXETER TO CONDUCT CONSTRUCTION MONITORING
		WOOD GUARDRAIL	HYD ©	HYD O WM	FIRE HYDRANT	<u>Utility</u>		Lavout and Materials
-00		PATH FENCE	PIV	⊡ PIV	WATER METER	СВ	CATCH BASIN	1. ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE SET OR RESET BY A LICENSED
$\sim \sim \sim \sim \sim$		TREE LINE	•	• (1)	POST INDICATOR VALVE	CMP	CORRUGATED METAL PIPE	LAND SURVEYOR (LLS).
>	>	CONSTRUCTION FENCE	GG		GAS GATE	со	CLEANOUT	2. IN ORDER TO PROVIDE VISUAL CLARITY ON THE PLANS, NOT ALL DEPICTED THEMS ARE DRAWN TO THEIR ACTUAL DIMENSIONS. REFER TO THE LABELED DIMENSIONS AND THE PROVIDED DETAILS FOR ACTUAL DESIGN INFORMATION.
	• •	STOCKADE FENCE	GM ⊡	GM ⊡	GAS METER	DCB	DOUBLE CATCH BASIN	Utilities
×		WIRE FENCE	E	● <sup>EMH</sup>	ELECTRIC MANHOLE		DRAIN MANHULE	1. THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE TOWN OF EXETER HAS NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS SHOWN ON THE PLANS. THE UTILITY INFORMATION
		RETAINING WALL	EM	EM ⊡	ELECTRIC METER		CONDUIT	SHOWN DOES NOT GUARANTEE THE ACTUAL EXISTENCE, SERVICEABILITY, OR OTHER DATA CONCERNING THE UTILITIES, NOR DOES IT GUARANTEE AGAINST THE POSSIBILITY THAT ADDITIONAL UTILITIES MAY BE PRESENT THAT ARE NOT SHOWN ON THE
		STREAM / POND / WATER COURSE	¢	*	LIGHT POLE	DIP	DUCTILE IRON PIPE	PLANS. PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY THAT THERE ARE NO INTERFERENCES WITH EXISTING UTILITIES INCLUDING ROUTES WITHIN THE PUBLIC RIGHTS OF WAY.
		DEMOLITION	$\bigcirc$	● <sup>™H</sup>	TELEPHONE MANHOLE	FES	FLARED END SECTION	2. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, OR EXISTING CONDITIONS DIFFER FROM THOSE SHOWN, SUCH THAT THE WORK CANNOT BE COMPLETED AS INTENDED. THE LOCATION, ELEVATION, AND SIZE OF THE
		SAWCUT	T	Т	TRANSFORMER PAD	FM	FORCE MAIN	UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED IN WRITING TO THE ENGINEER FOR THE RESOLUTION OF THE CONFLICT. CONTRACTOR'S FAILURE TO NOTIFY PRIOR TO
		SILT FENCE SILT SOCK / STRAW WATTLE	-0-	•	UTILITY POLE	F <b>&amp;</b> G	FRAME AND GRATE	PERFORMING ADDITIONAL WORK RELEASES THE TOWN OF EXETER AND OTHER PROJECT PARTNERS FROM OBLIGATIONS FOR ADDITIONAL PAYMENTS WHICH OTHERWISE MAY BE WARRANTED TO RESOLVE THE CONFLICT.
	<b></b>	TURBIDITY CURTAIN	0—	•	GUY POLE	F&C	FRAME AND COVER	3. NOTIFY ALL CORPORATIONS, COMPANIES, INDIVIDUALS, OR LOCAL AUTHORITIES OWNING OR HAVING JURISDICTION OVER UTILITIES RUNNING TO THROUGH OR ACROSS AREAS TO BE AFFECTED BY CONSTRUCTION ACTIVITIES
4	<u> </u>	MINOR CONTOUR	Н Нн	⊥ <u>⊥</u> ⊓	GUY WIRE & ANCHOR	GI	GUTTER INLET	4. LOCATE AND IDENTIFY EXISTING UTILITIES THAT ARE TO REMAIN AND PROTECT THEM FROM DAMAGE.
— — 20— —	20	MAJOR CONTOUR	PB ©	PB ©	HAND HULL PULL BOX	G I HNPF	UNEADE INAM	Existing Conditions Information
DYL	DYL	DOUBLE YELLOW LINE	Mato	hline		НН	HANDHOLE	1. BASE PLAN: SEE EXISTING CONDITIONS PLANS, SHEET C-2 AND SHEET C-3.
SL	SL	STOP LINE		······································	MATCHLINE	нพ	HEADWALL	A. THE PROPERTY LINES SHOWN HEREON ARE BASED ON DEEDS AND PLANS OF RECORD AND THE TOWN OF EXETER GIS
		CROSSWALK				HYD	HYDRANT	B. THE EXISTING CONDITIONS SHOWN HEREON ARE BASED ON SURVEYS BY OTHERS TOWN OF EXETER GIS AND
		ACCESSIBLE CURB RAMP				INV	INVERT ELEVATION	SUPPLEMENTED BY AN ON-THE-GROUND INSTRUMENT SURVEY BY VHB, INC. BETWEEN JULY & AUGUST 2011.
L. L. VAN	چر معر	ACCESSIBLE PARKING VAN-ACCESSIBLE PARKING				I= LP	INVERT ELEVATION LIGHT POLE	C. THE EXISTING CONDITIONS TOPOGRAPHY DEPICTED AT THE PROPERTY AT 23 WATER STREET WAS TAKEN FROM THE COASTAL LIDAR DATA SET (ACQUIRED WINTER 2010/SPRING 2011) OBTAINED FROM NH GRANIT (NEW HAMPSHIRE STATEWIDE GEOGRAPHIC INFORMATION SYSTEM (GIS) CLEARINGHOUSE) AND NOT FROM ON THE GROUND SURVEY.

MES METAL END SECTION

PAVED WATER WAY

RIM ELEVATION

UNDERGROUND

UTILITY POLE

SEWER MANHOLE

POLYVINYLCHLORIDE PIPE

REINFORCED CONCRETE PIPE

TAPPING SLEEVE, VALVE AND BOX

POST INDICATOR VALVE

PWW

PVC

ΡIV

RCP

SMH

TSV

UG

UP

R =

- CONTRACTOR'S OPERATIONS TO THEIR ORIGINAL
- ER MEDIA ARE ENCOUNTERED DURING OR OTHER EVIDENCE, STOP WORK IN THE IATERIAL, AND NOTIFY THE ENGINEER CAN BE TAKEN.
- E RESPONSIBLE FOR CLEANUP, REPAIRS AND
- CONTRACTOR AT THEIR OWN EXPENSE.
- IMPACTS TO OFF SITE AREAS, AND SREPAIR ACENT PROPERTY OWNERS. DAMAGE RESULTING EIR OWN EXPENSE.
- TERMS "ENGINEER" AND "MONITOR" SHALL BE OF EXETER TO CONDUCT CONSTRUCTION

- TION SHALL BE SET OR RESET BY A LICENSED
- EMS ARE DRAWN TO THEIR ACTUAL DIMENSIONS. DESIGN INFORMATION.

- APPROXIMATE REPRESENTATION ONLY. THE HOWN ON THE PLANS. THE UTILITY INFORMATION THER DATA CONCERNING THE UTILITIES, NOR Y BF PRESENT THAT ARE NOT SHOWN ON THE THAT THERE ARE NO INTERFERENCES WITH
- RK, OR EXISTING CONDITIONS DIFFER FROM THE LOCATION, ELEVATION, AND SIZE OF THE ACTOR, AND THE INFORMATION FURNISHED IN TOR'S FAILURE TO NOTIFY PRIOR TO PROJECT PARTNERS FROM OBLIGATIONS FOR THE CONFLICT.
- OWNING OR HAVING JURISDICTION OVER NSTRUCTION ACTIVITIES.
- THEM FROM DAMAGE.

- - NS OF RECORD AND THE TOWN OF EXETER GIS
- OTHERS, TOWN OF EXETER GIS AND INC. BETWEEN JULY & AUGUST 2011.
- 23 WATER STREET WAS TAKEN FROM THE INED FROM NH GRANIT (NEW HAMPSHIRE ND NOT FROM ON THE GROUND SURVEY.
- D. THE BATHYMETRY NORTHWEST OF THE GREAT DAM IS BASED ON AN ON-THE-GROUND SURVEY BY VHB, INC. BETWEEN JULY AND AUGUST 2011.
- E. THE BATHYMETRY SOUTHEAST OF THE GREAT DAM IS BASED ON AN ON-THE-GROUND SURVEY BY VHB, INC. IN SEPTEMBER 2014.
- F. THE HORIZONTAL DATUM IS BASED ON NH GRID. THE ELEVATIONS SHOWN HEREON REFER TO NAVD 1988 GEOID 12A.
- G. WETLAND BOUNDARIES DEPICTED ON PLANS ARE COWARDIN CLASSIFICATIONS COMPLETED BY A VHB WETLAND SCIENTIST USING AERIAL ORTHOIMAGERY AND NOT ON-THE-GROUND SURVEY.

GEOTECHNICAL DATA INCLUDING TEST PIT AND BORING LOCATIONS AND ELEVATIONS WERE OBTAINED FROM PARE CORPORATION AND ARE DETAILED IN THEIR REPORT TITLED "GEOTECHNICAL DESIGN BASIS REPORT, PROPOSED REMOVAL OF GREAT DAM, EXETER RIVER, EXETER, NEW HAMPSHIRE", DATED DECEMBER 2014. BORING LOCATIONS ARE DEPICTED ON SHEET C-2. BORING LOG DATA IS PROVIDED IN THE FINAL REPORT AND CAN BE OBTAINED BY CONTACTING THE TOWN OF EXETER ENGINEER, MR. PAUL VLASICH AT 603-773-6160.

## Notes:

Demolition

- 1.1. PERMITS FOR TRANSPORT AND DISPOSAL OF DEBRIS. 1.2. DEMOLITION PROCEDURES AND OPERATIONAL SEQUENCE. 1.3. CALCULATIONS
- ORDINANCES AND STATUTES.
- WORK.
- OR DISPOSAL OF ASBESTOS OR OTHER HAZARDOUS MATERIALS.
- OWNER'S REPRESENTATIVE.
- TO THE ENGINEER.
- RETURN ADJACENT AREAS TO THE CONDITION WHICH EXISTED PRIOR TO START OF WORK.
- SUBSTANCE.

Erosion Control

- 1.
- SEDIMENTATION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT.
- ARE COVERED, SEEDED, OR OTHERWISE STABILIZED TO PREVENT EROSION.
- EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS.
- APPROXIMATELY 1 INCH.
- SEEDING SHALL BE STRAW MULCHED.
- 7. APPLY WATER AS NEEDED TO CONTROL DUST
- ALONG DOWNHILL SIDE OF STOCKPILES.
- DOES NOT CARRY SILT, SEDIMENT, AND OTHER DEBRIS OUTSIDE OF THE LIMITS OF WORK.
- 10. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: A A MINIMUM OF 85% VECETATED COVER HAS BEEN ESTABLISHED.
- A DETERMINATION AS TO WHETHER AN AREA IS STABLE.
- GRADE.
- 13. ALL PERMANENT AND TEMPORARY SEEDING SHALL BE FREE OF NOXIOUS WEED SEED.
- NITROGEN.
- CONSTRUCTION.

### Winter Construction

- MELTS, DO NOT INSTALL OVER ACCUMULATED SNOW OR FROZEN GROUND.
- ARE DISTURBED AFTER OCTOBER 15TH,

### State Regulations

- 2. RSA 482-A, WETLAND DREDGE AND FILL, NH DEPARTMENT OF ENVIRONMENTAL SERVICES, WETLANDS BUREAU.
- 3. CLEAN WATER ACT, SECTION 401 WATER QUALITY CERTIFICATION, NH DEPARTMENT OF ENVIRONMENTAL SERVICES,
- WATERSHED MANAGEMENT BUREAU.
- BUREAU.

### Federal Regulations

- 2. USFWS ENDANGERED SPECIES ACT AND BIOLOGICAL OPINION.

DIVISION OF HISTORICAL RESOURCES).

- Signage

1. SUBMIT THE FOLLOWING INFORMATION TO THE ENGINEER FOR REVIEW BEFORE COMMENCING WORK:

DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS,

3. THE DEMOLITION LIMITS DEPICTED ON THE PLANS ARE INTENDED TO AID THE CONTRACTOR DURING THE BIDDING AND CONSTRUCTION PROCESS AND IS NOT INTENDED TO DEPICT EACH AND EVERY ELEMENT OF DEMOLITION. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING THE DETAILED SCOPE OF DEMOLITION BEFORE SUBMITTING ITS BID/PROPOSAL TO PERFORM THE WORK AND SHALL MAKE NO CLAIMS AND SEEK NO ADDITIONAL COMPENSATION FOR CHANGED CONDITIONS OR UNFORESEEN OR LATENT SITE CONDITIONS RELATED TO ANY CONDITIONS DISCOVERED DURING EXECUTION OF THE

4. UNLESS OTHERWISE SPECIFICALLY PROVIDED ON THE PLANS OR IN THE SPECIFICATIONS, THE ENGINEER HAS NOT PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF HAZARDOUS MATERIALS, TOXIC WASTES OR POLLUTANTS AT THE PROJECT SITE. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY CLAIMS OF LOSS, DAMAGE, EXPENSE, DELAY, INJURY OR DEATH ARISING FROM THE PRESENCE OF HAZARDOUS MATERIAL AND CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE ENGINEER FROM ANY CLAIMS MADE IN CONNECTION THEREWITH. MOREOVER, THE ENGINEER SHALL HAVE NO ADMINISTRATIVE OBLIGATIONS OF ANY TYPE WITH REGARD TO ANY CONTRACTOR AMENDMENT INVOLVING THE ISSUES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT

5. CEASE OPERATIONS IMMEDIATELY IF ANY DAMAGE, SETTLEMENT, OR OTHER ADVERSE EFFECT ON ADJACENT STRUCTURES OCCUR. HOWEVER, IF AN UNSAFE CONDITION IS CREATED THAT WOULD POTENTIALLY CAUSE INJURY TO PERSONS OR UNDUE HARM TO PROPERTIES, TAKE WHATEVER MEASURES ARE WARRANTED TO PREVENT SUCH INJURY OR HARM. IMMEDIATELY NOTIFY THE ENGINEER AND REGULATORY AGENCIES. DO NOT RESUME OPERATIONS UNTIL CONDITIONS ARE CORRECTED, DAMAGE REPAIRED, AND APPROVAL HAS BEEN RECEIVED FROM THE APPROPRIATE AUTHORITIES AND THE

OBTAIN WRITTEN PERMISSION FROM ADJACENT PROPERTY OWNERS WHEN DEMOLITION EQUIPMENT WILL TRANSVERSE, INFRINGE UPON, OR AFFECT ACCESS TO THEIR PROPERTY. COPIES OF THE PERMISSION DOCUMENTS SHALL BE SUBMITTED

7. PROVIDE HOSES AND WATER CONNECTIONS AND SPRAY WATER ON DEMOLITION DEBRIS TO MINIMIZE DUST.

8. CLEAN ADJACENT STRUCTURES AND IMPROVEMENTS OF DUST, DIRT, AND DEBRIS CAUSED BY DEMOLITION OPERATIONS.

9. ALL HAZARDOUS WASTE REMOVAL SHALL BE PERFORMED BY A HAZARDOUS WASTE CONTRACTOR QUALIFIED AND DULY LICENSED IN THE STATE OF NEW HAMPSHIRE TO REMOVE, TRANSPORT, AND DISPOSE OF EACH TYPE OF HAZARDOUS

INSPECT AND MAINTAIN EROSION CONTROL MEASURES WITHIN 24 HOURS AFTER EACH STORM EVENT (0.25" OF RAINFALL OR GREATER PER 24 HOUR PERIOD) AND DISPOSE OF DEPOSITED SEDIMENTS IN AN UPLAND AREA SUCH THAT THEY DO NOT ENCUMBER OTHER DRAINAGE STRUCTURES, EROSION CONTROL MEASURES AND PROTECTED AREAS.

2. CONTROL CONSTRUCTION SUCH THAT SEDIMENTATION DOES NOT AFFECT REGULATORY PROTECTED AREAS, WHETHER SUCH

3. PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF TIME BEFORE THEY

4. UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER, REMOVE AND DISPOSE OF

5. TEMPORARILY SEED AND MULCH AREAS REMAINING UNSTABILIZED FOR A PERIOD OF MORE THAN 7 DAYS. CLEAN, WEED FREE, STRAW MULCH SHALL BE APPLIED AT A MINIMUM RATE OF 1-1/2 TONS/ACRE, WHICH EQUALS A THICKNESS OF

6. PERMANENT SEEDING SHALL OCCUR BETWEEN APRIL 1 AND JUNE 1, AND/OR BETWEEN AUGUST 15 AND OCTOBER 15. ALL

8. TEMPORARILY SEED AND MULCH SOILS TO BE STOCKPILED FOR A PERIOD OF MORE THAN 7 DAYS. INSTALL SILT FENCING

9. PROVIDE NECESSARY EROSION CONTROL MEASURES TO INSURE THAT SURFACE WATER RUNOFF FROM UNSTABILIZED AREAS

B. A MINIMUM OF 3-IN OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIPRAP. HAS BEEN INSTALLED: EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED. THE ENGINEER SHALL BE RESPONSIBLE FOR MAKING

11. ALL DITCHES, SWALES, AND DRAINAGE BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

12. LOAM, SEED, MULCH, OR MAT FILL ALL CUT AND FILL SLOPES, IF REQUIRED, WITHIN 72 HOURS OF ACHIEVING FINISHED

14. NO FERTILIZERS (EXCEPT LIMESTONE) SHALL BE USED WITHIN 25 FEET OF THE RIVER. FROM 25-250 FEET, LOW PHOSPHATE, SLOW RELEASE NITROGÉN FERTILIZER MAY BE USED. THESE FERTILIZERS MUST BE GUARANTEED ON THE PACKAGE LABEL TO CONTAIN NOT MORE THAN 2 PERCENT PHOSPHOROUS AND AT LEAST 50 PERCENT SLOW RELEASE

15. INSTALL STABILIZED CONSTRUCTION ENTRANCES AT CONSTRUCTION ENTRANCES. DETERMINE FINAL LOCATION PRIOR TO

ALTHOUGH WINTER CONSTRUCTION IS NOT ANTICIPATED, STABILIZE ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH. STABILIZATION METHODS INCLUDE SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE AND SECURED WITH ANCHORED NETTING, ELSEWHERE. COMPLETE THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING IN ADVANCE OF THAW OR SPRING

2. TEMPORARILY STABILIZE ALL DITCHES OR SWALES, WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS, WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH

1. ALL WORK SHALL COMPLY WITH PERMIT CONDITIONS OUTLINED IN NHDES WETLANDS AND NON-SPECIFIC PERMIT. CONDITIONS IN PERMIT SHALL GOVERN OVER PLANS UNLESS OTHERWISE DIRECTED OR APPROVED BY THE ENGINEER.

4. RSA 483-B, COMPREHENSIVE SHORELAND PROTECTION ACT, NH DEPARTMENT OF ENVIRONMENTAL SERVICES, WETLAND

1. CLEAN WATER ACT, SECTION 404, WETLAND DREDGE AND FILL PERMIT, US ARMY CORPS OF ENGINEERS.

3. NATIONAL HISTORIC PRESERVATION ACT, SECTION 106 CONSULTATION, NH STATE HISTORIC PRESERVATION OFFICE (NH

1. CONTRACTOR SHALL INSTALL A PROJECT SIGN IDENTIFYING THE OWNER, DESIGN ENGINEER AND FUNDING PARTNERS IN A PROMINENT LOCATION WITHIN THE LIMIT OF WORK. THE SIGN SHALL HAVE MINIMUM DIMENSIONS OF 4 FEET BY 6 FEET AND SHALL MEET THE REQUIREMENTS OUTLINED IN SPECIAL PROVISION 692 OF THE SPECIFICATIONS.



Watertown, MA 02471 617.924.1770 f 617.924.2286

Engineers Scientists

Planners

No.		Revision		Date	Appvd.
Designe	<sup>ed by</sup> TM	Drawn by	JB	Checked by J.	SA
CAD ch	ecked by TM	1	Approved by	JSA	
Scale			Date 03/2	23/16	
	T'-1				

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Drawing Title

Legend and General Notes



Drawing Number

1 12

Project Numbe 52151.04





Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Issued for

Drawing Title

## **Existing Conditions Plan**



Engineers Scientists Planners Designers













HORIZONTAL

VERTICAL SCALE IN FEET

5

5

10









## PUMP HOUSE PROFILE



No.		Revision		Date	Appvd.
Designe	ed by TM	Drawn by	JB	Checked by	'SA
CAD checked by TM			Approved by	JSA	
Scale	1"= 10'		Date 03/2	23/16	
n · ·	T'11				

Great Dam Removal and Exeter River Restoration

Exeter, New Hampshire

Construction

Drawing Title

## **Existing Conditions Plan**



Drawing Number

Sheet of 3 12

Project Number 52151.04



HIGH-FLOW CONTINGENCY PLANS. 2. PROVIDE A DETAILED WORK PLAN INCLUDING FINAL CONSTRUCTION SCHEDULE AND METHODS TO ENGINEER, TOWN AND NHDES AT LEAST TWO WEEKS PRIOR TO CONSTRUCTION. DOCUMENT DETAILS OF PROPOSED RIVER DIVERSION, COFFERDAM CONSTRUCTION, CONSTRUCTION PHASING AND TEMPORARY EROSION CONTROL MEASURES TO BE IMPLEMENTED. ADDRESS THE ENTIRE WATER MANAGEMENT AND CONTROL PLAN, DAM REMOVAL AND RIVER RESTORATION PORTIONS OF THE PROJECT.

### Timing

- 1. IN-STREAM WORK FOR DAM REMOVAL SHALL NOT COMMENCE UNTIL DRY WEATHER IS FORECASTED, GENERALLY FOR AT LEAST 3 TO 4 DAYS. SHOULD A SIGNIFICANT (GREATER THAN 0.5 INCH) RAINFALL EVENT OCCUR WHILE WORK IS BEING CONDUCTED IN THE RIVER, REMOVE ALL EQUIPMENT FROM THE RIVER UNTIL THE HIGH RIVER FLOW SUBSIDES.
- 2. IN-STREAM WORK SHALL ADHERE TO REQUIREMENTS OUTLINED IN THE NHDES WETLANDS AND NON-SPECIFIC PERMIT

- 2. STRIP LOAM WITHIN AREAS DISTURBED BY GRADING AND/OR EQUIPMENT ACCESS AND
- STOCKPILE FOR LATER RESTORATION. DO NOT SALVAGE TOPSOIL FROM AREAS WITH NON-NATIVE, INVASIVE SPECIES.
- 4. DRAW DOWN THE IMPOUNDMENT BY OPENING THE LOW LEVEL OUTLET ON THE EAST BANK. WET VS. DRY CONSTRUCTION IN THE FINAL SCHEDULE & METHODS. METHODS TO BE
- 3. GRADE THE EASTERN BANK AT THE CAUSEWAY TO ALLOW FOR EQUIPMENT ACCESS. 5. CONDUCT WORK IN THE DRY TO THE EXTENT POSSIBLE TO MINIMIZE TURBIDITY. ADDRESS REVIEWED AND ACCEPTED BY THE ENGINEER AND NHDES.
- 6. INSTALL A TEMPORARY COFFERDAM ON THE UPSTREAM FACE OF THE DAM TO ALLOW FOR ADEQUATE DE-WATERING, SITE PREPARATION, AND DEMOLITION OF THE DAM. CHOOSE THE COFFERDAM CONSTRUCTION TYPE AS WELL AS METHODS FOR MANAGING AND CONTROLLING WATER THROUGHOUT THE CONSTRUCTION PERIOD, BUT THE DESIGN IS SUBJECT TO REVIEW AND ACCEPTANCE BY THE ENGINEER AND NHDES WETLANDS BUREAU.
- 7. INSTALL TIMBER ACCESS BRIDGE FROM EAST BANK TO WEST BANK. PLACE THE COFFERDAM, STARTING FROM THE WEST BANK TO BEGIN DEMOLITION OF DAM ALONG WEST BANK MOVING TOWARD THE EAST ABUTMENT. THE COFFERDAM SHOULD EXTEND FAR ENOUGH DOWNSTREAM TO PREVENT BACKWATER FROM ENTERING THE DAM REMOVAL AREA.
- 8. DEWATER TURBID WATER, IF REQUIRED, BY DISCHARGING TO A STABILIZED SEDIMENT



- 3. INSTALL TIMBER MATS & RAMP ACCESS BRIDGE FROM EAST BANK TOWARDS WEST BANK 4. REMOVE LOWER FISH WEIR IN WEST SIDE OF RIVER

ENGINEER.

1. DRAW DOWN IMPOUNDMENT

- 5. REMOVE FISH LADDER 6. REMOVE CONCRETE DAM IN WEST SIDE OF RIVER
- 7. GRADE CHANNEL WITHIN COFFER DAM AREA

(OUTSIDE OF THE TEMPORARY COFFERDAM).

Phase 1 - Suggested Sequence of Construction

SHOWN (APPROX BANKFULL STORM ELEVATION)

8. SEED AND RESTORE WESTERN BANKS AS SHOWN ON SHEET C-10.

9. AT THE DIRECTION OF THE ENGINEER, INSTALL A TURBIDITY CURTAIN AND/OR FLOATING

DEBRIS BOOM TO CONTAIN SUSPENDED SEDIMENT DURING DREDGING OPERATIONS

2. INSTALL COFFER DAM (SAND BAGS, PORTADAM, OR APPROVED EQUAL) TO ALLOW WORK ON

WEST SIDE OF CHANNEL. COFFER DAM HEIGHT TO TRANSITION BETWEEN ELEVATIONS

- 2. ADJUST TIMBER MATS IF NECESSARY
- 3. REMOVE FISH WEIR IN EAST SIDE OF RIVER
- 4. REMOVE CONCRETE DAM IN EAST SIDE OF RIVER
- 5. SAWCUT CONC. AT DAM HEADWORKS AND REMOVE GEAR WORKS FOR FUTURE USE 6. SEAL PENSTOCK AND REMOVE LOW FLOW OUTLET
- 7. GRADE REMAINING CHANNEL WITHIN COFFER DAM AREA
- 8. SEED AND RESTORE EASTERN BANKS AS SHOWN ON SHEET C-10.

Phase 3 - Suggested Sequence of Construction 1. FOLLOWING FIRST SPRING MIGRATION SEASON POST CONSTRUCTION, ADJUST GRADING AND BOULDER PLACEMENT AT DIRECTION OF ENGINEER



Engineers

**Scientists** 

No.		Revision		Date	Appvd.
Designe	ed by TM	Drawn by	JB	Checked by J	SA
CAD ch	ecked by Th	1	Approved by	JSA	
Scale	1"=30'		Date 03/2	23/16	

## Great Dam Removal and **Exeter River Restoration**

Exeter, New Hampshire

Construction

Drawing Title

## Staging and **Construction Sequence**



Drawing Numbe

## 4 12

Project Numbe 52151.04





Engineers Scientists

Planners

f 617.924.2286

No.		Revision		Date	Appvd.
Designe	<sup>ed by</sup> TM	Drawn by	JB	Checked by	SA
CAD ch	ecked by 7/	1	Approved by	JSA	
Scale	1"=20'		Date 03/2	23/16	
Project	Title				

## Great Dam Removal and **Exeter River Restoration**

Exeter, New Hampshire

Construction

Drawing Title

## Structure Demolition Plan







Engineers

Scientists

f 617.924.2286

No.		Revision		Date	Appvd.
Designed by TM Drawn by			JB	Checked by	SA
CAD checked by TM			Approved by	JSA	
Scale 1"=20'			Date 03/2	23/16	
Project	Title				

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Drawing Title

**River Channel** Grading Plan





-70.00

-60.00





















NOTE: CROSS SECTIONS ARE DRAWN LOOKING DOWNSTREAM WITH THE EAST BANK SHOWN ON THE RIGHT AND THE WEST BANK SHOWN ON THE LEFT

	Legend
	EXISTING SURFACE
	PROPOSED SURFACE
· <del></del>	PROPOSED BANKFULL WSE (1.5 )
	APPROXIMATED QUARTZITE BED
, , <u>-</u>	APPROXIMATED WEATHERED RC

Engineers Scientists Planners Designers





_					
No.		Revision		Date	Appvd.
Designed by TM Drawn by			JB	Checked by	SA
CAD checked by TM			Approved by	JSA	
Scale 1"=20'			Date 03/2	23/16	
Project	Title				

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Drawing Title

## **River Channel Cross Sections**













**Granite Revetment at Green Bean on Water (STA 1+25)** N.T.S.

N.T.S.



No. Revision Date Appvd. JSA Designed by TM Drawn by JB CAD checked by Approved by JSA ΤM Scale NTS Date 03/23/16 Project Title

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Issued for

Drawing Title

Typical **Cross Sections** 



Drawing Number

Sheet of 8 12

Project Number 52151.04



FRANKLIN ST. DRY HYDRANT PLAN









## PUMP HOUSE PROFILE



No.		Revision		Date		Appvd.
Designe	ed by TM	Drawn by	JB	Checked by	JS	SA
CAD ch	ecked by Th	1	Approved by	' JSA		
Scale	1"=10'		Date 03/	23/16		

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Drawing Title

Conceptual Intake Designs

# C-9 Sheet of 9 12

Drawing Number

Project Number 52151.04



![](_page_10_Picture_12.jpeg)

![](_page_10_Figure_14.jpeg)

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Construction

Issued for

Drawing Title

## Restoration and Planting Plan

![](_page_10_Picture_19.jpeg)

Project Number 52151.04

LD-PRG.DWG

Engineers Scientists Planners

![](_page_11_Figure_0.jpeg)

![](_page_11_Figure_2.jpeg)

N.T.S.

N.T.S.

**Turbidity Curtain** N.T.S.

Engineers Scientists Planners Designers

![](_page_11_Figure_10.jpeg)

![](_page_11_Figure_11.jpeg)

## Great Dam Removal and **Exeter River Restoration**

Exeter, New Hampshire

Construction

Issued for

Details

Drawing Title

![](_page_11_Picture_16.jpeg)

Drawing Number

11 12

Project Number 52151.04

GALVANIZED #24 SAFETY HOOK -STRESS PLATE (TO REMOVE WATER/ PRESSURE FROM FLOATS) CONNECTOR SEAL TOP LOAD LINE 5/16 VINYL COATED CABLE /FLOATATION  $\ge$ FOLDS EVERY 6 FEET **b-0-0-0**-5/16 IN. CHAIN O BALLAST AND STRESS PLATE LOAD LINE -----

1. TURBIDITY CURTAIN SHALL BE TYPE II OR TYPE III AND SHALL ALLOW CONTINUOUS FLOW THROUGH OF 2. CONTRACTOR SHALL SUBMIT PRODUCT DATA SHEETS TO ENGINEER FOR APPROVAL.

Notes:

![](_page_12_Figure_0.jpeg)

## 7.5' High x 14.0' Wide Penstock Closure Stone Wall (Reinforced CMU Wall) N.T.S.

STONE CLASS	STONE SIZE (IN)
D95	24 - 40
D84	18 - 24
D50	10 - 15
D30	5 – 8
D16	2 - 4

NOTES:

- 1. CONTRACTOR SHALL ADD 10% SAND TO COBBLE - BOULDER MIX.
- 2. CONTRACTOR TO PLACE MINIMUM 30 INCH DEPTH OF SPECIFIED BED MATERIAL.

## **Cobble-Boulder Bed Material Specification**

N.T.S.

\*\*\* MINIMUM X-Y-Z DIMENSIONS FOR ALL STRUCTURE STONES SHALL MEET THE MINIMUM SIZE REQUIREMENTS GIVEN IN THE TABLE BELOW.

![](_page_12_Figure_10.jpeg)

Boulder Axis Detail	
N.T.S.	

![](_page_12_Figure_12.jpeg)

![](_page_12_Figure_13.jpeg)

**Riffle Crest Detail** N.T.S.

![](_page_12_Figure_16.jpeg)

![](_page_12_Figure_17.jpeg)

![](_page_12_Picture_18.jpeg)

								-
								-
								-
								-
								-
								-
								-
								-
No.		Revision			Date		Appvd.	-
Designe	ed by TM	Drawn by	JB		Checked by	JS	5A	-
CAD ch	ecked by	TM	Appro	ved by	JSA			-
Scale	NTS		Date	03/2	23/16			_
Project	Titla							-

Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire Issued for

Construction

Details (2)

Drawing Title

![](_page_12_Picture_24.jpeg)

Drawing Number

Sheet of 12 12

Project Number 52151.04

LD—DT.DWG