

# **Funding Partner Information**



# **NHDES, Coastal Program**



# NHDES, Aquatic Resource Mitigation Fund



# NH State Conservation Committee, Conservation Grant Program

# Permits

NH Department of Environmental Services, RSA 482-A, Wetlands Permit: 2015-00XXX

NH Department of Environmental Services, RSA 485-A:17, Terrain Alteration: General Permit by Rule Env-Wq 1503.03(f)

NH Department of Environmental Services, RSA 483-B, Shoreland Protection: Permit Exemption per RSA 483-B:5-b,IV

NH Department of Environmental Services, Clean Water Act, Section 401 Certification: WQC #2012-404P-002

US Army Corps of Engineers, Clean Water Act, Section 404 Permit: NAE-2015-0XXXX

US Environmental Protection Agency, National Pollutant Discharge Elimination System, General Permit for Discharges from Construction Activities: Permit No. NHR120000

National Historic Preservation Act, Section 106 Memorandum of Agreement: NHDHR R&C #3280

# Great Dam Removal and Exeter River Restoration

# Exeter, New Hampshire


# **Property Owners**

# **Town of Exeter**

10 Front Street Exeter, NH 03883 Phone: 603-773-6157 · Fax: 603-772-1355

Paul Vlasich, PE Town Engineer





## Site Location Map



# Site Plans

Issued for	Permitting		
Date Issued	December 7, 2015		
Latest Issue	December 7, 2015		

# FOR PERMIT USE ONLY NOT FOR CONSTRUCTION

Sheet Index					
Number	Drawing Title	Latest Issue			
C-1	Legend and General Notes	12/07/15			
C-2	Existing Conditions Plan	12/07/15			
C-3	Existing Conditions Plan	12/07/15			
C-4	Staging & Construction Sequencing	12/07/15			
C-5	Structure Demolition Plan	12/07/15			
C-6	River Channel Grading Plan	12/07/15			
C-7	River Channel Cross Sections	12/07/15			
C-8	Typical Cross Sections	12/07/15			
C-9	Conceptual Intake Designs	12/07/15			
C-10	Restoration and Planting Plan	12/07/15			
C-11	Wetland Impact Plan	12/07/15			
C-12	Wetland Impact Plan	12/07/15			
C-13	Details	12/07/15			
C-14	Details	12/07/15			

# Reference Drawings

Number	Drawing Title	Latest Issue
SV-1	Existing Conditions Plan of Land	3/23/2015

VHB Project No. 52151.04

Issued for: Permitting

		Lea	gend				Abbreviations
Exist.	Prop.		Exist.	Prop.		Genera	al
		PROPERTY LINE			CONCRETE	4044	ADANDON.
_		LIMIT OF WORK	(4.5 M. \$50000)	(4,5 m, \$400 h)	HEAVY DUTY PAVEMENT	ABAN	ABANDON
		RIGHT-OF-WAY/PROPERTY LINE			RIPRAP	ACR	ACCESSIBLE CURB RAMP
		EASEMENT	020020		CONSTRUCTION ENTRANCE	ADJ	ADJUST
		BUILDING SETBACK		<u> </u>		APPROX	APPROXIMATE
		PARKING SETBACK	27.35 TC×	27.35 TC×	TOP OF CURB ELEVATION	BIT	BITUMINOUS
10+00	10+00	BASELINE	26.85 BC×	26.85 BC×	BOTTOM OF CURB ELEVATION	BS	BOTTOM OF SLOPE
·		CONSTRUCTION LAYOUT	132.75 ×	132.75 ×	SPOT ELEVATION	BWLL	BROKEN WHITE LANE LINE
		ZONING LINE	45.0 TW 38.5 BW	45.0 TW × 38.5 BW	TOP & BOTTOM OF WALL ELEVATION	CONC	CONCRETE
		TOWN LINE	<b>+</b>	<b>+</b>	BORING LOCATION	DYCL	DOUBLE YELLOW CENTER LINE
		TOWN LINE			TEST PIT LOCATION		
WTL		WETLAND LINE	<b>○</b> <sup>MW</sup>	→ MW	MONITORING WELL	EL	ELEVATION
100-YR		100-YEAR FLOODPLAIN			PENSTOCK	ELEV	ELEVATION
FLD		REGULATORY FLOODWAY	110			EX	EXISTING
——————————————————————————————————————		ORDINARY HIGH WATER	———UD <i>—</i> —— 12 <b>"</b> D	——ບບ—— 12″D—►	UNDERDRAIN	EXIST	EXISTING
тов		TOP OF BANK			DRAIN	FDN	FOUNDATION
SP50		50' SHORELINE PROTECTION SETBACK	6"RD 12"S	12"S	ROOF DRAIN	FFE	FIRST FLOOR ELEVATION
SP150		150' SHORELINE PROTECTION SETBACK	FM	FM	SEWER	FLD	REGULATORY FLOODWAY
					FORCE MAIN	GRAN	GRANITE
		250' SHORELINE PROTECTION SETBACK	——— OHW ———	—— OHW ——	OVERHEAD WIRE		
			6"W	6"W	WATER	GTD	GRADE TO DRAIN
		GRAVEL ROAD	4"FP	——4"FP——	FIRE PROTECTION	LA	LANDSCAPE AREA
<u>EOP</u>		EDGE OF PAVEMENT		2"DW	DOMESTIC WATER	MAX	MAXIMUM
BB	BB	BITUMINOUS BERM	3"G	G	GAS	MIN	MINIMUM
BC	BC	BITUMINOUS CURB	——Е——	——E——	ELECTRIC	NIC	NOT IN CONTRACT
	CC	CONCRETE CURB	STM	STM	STEAM	NTS	NOT TO SCALE
	CG	CURB AND GUTTER	——т—	T	TELEPHONE	ОНМ	ORDINARY HIGH WATER
	ECC	EXTRUDED CONCRETE CURB	——FA——	——FA——	FIRE ALARM		
	MCC	MONOLITHIC CONCRETE CURB		——CATV——	CABLE TV	PERF	PERFORATED
	PCC	PRECAST CONC. CURB	<b>FIR</b>		OATOU BAOW	PROP	PROPOSED
SGE	SGE	SLOPED GRAN. EDGING		<b>=</b>	CATCH BASIN	REM	REMOVE
VGC	VGC	VERT. GRAN. CURB			DOUBLE CATCH BASIN	RET	RETAIN
		LIMIT OF CURB TYPE			GUTTER INLET	R&D	REMOVE AND DISPOSE
	<b>1</b> 1		<b>(</b> )	0	DRAIN MANHOLE	R <b>&amp;</b> R	REMOVE AND RESET
(11111111.		BUILDING	=TD=	<del></del>	TRENCH DRAIN	SP50	SHORELINE PROTECTION, 50'
	<b>7</b> ⊲EN	BUILDING ENTRANCE	_co	co CO	PLUG OR CAP		
		LOADING DOCK	•		CLEANOUT	SP150	SHORELINE PROTECTION, 150'
_/\		BOLLARD		•	FLARED END SECTION	SWEL	SOLID WHITE EDGE LINE
D	D	DUMPSTER PAD -			HEADWALL	SWLL	SOLID WHITE LANE LINE
<del></del>	<u></u>	SIGN	©S	©3 <b>●</b>	SEWER MANHOLE	TOB	TOP OF BANK
<del></del>	<u>.</u>	DOUBLE SIGN	⊚ W ⊚	wv	CURB STOP & BOX	TS	TOP OF SLOPE
		BOODLE SION		•	WATER VALVE & BOX	TYP	TYPICAL
	т т_	STEEL GUARDRAIL	TSV —●►	TSV <del>→•</del>	TAPPING SLEEVE, VALVE & BOX	WSE	WATER SURFACE ELEVATION
		WOOD GUARDRAIL	<b>↔</b> _HYD	₩ HYD	SIAMESE CONNECTION	WSL	WATER SORTAGE ELEVATION
			WM	<b>⊙</b> WM	FIRE HYDRANT	<b>Utility</b>	
=	= = =	PATH	•	•	WATER METER	СВ	CATCH BASIN
$\sim$	<del>-</del>	Fence Tree line	PIV	PIV <b>●</b>	POST INDICATOR VALVE	СМР	CORRUGATED METAL PIPE
, , , , , , , , , , , , , , , , , , ,	→—	CONSTRUCTION FENCE	<b>(</b>		WATER WELL		CLEANOUT
	<b>→</b>	TREE PROTECTION FENCE	GG <b>O</b>	GG <b>O</b>	GAS GATE	CO	
		STOCKADE FENCE	GM ⊡	GM ⊡	GAS METER	DCB	DOUBLE CATCH BASIN
×	×_	WIRE FENCE		EMH		DMH	DRAIN MANHOLE
	$\infty$	STONE WALL	E) FM		ELECTRIC MANHOLE	CIP	CAST IRON PIPE
		RETAINING WALL	EM ⊡	EM ⊡	ELECTRIC METER	COND	CONDUIT
		STREAM / POND / WATER COURSE COFFER DAM/SAND BAGS	\$	*	LIGHT POLE	DIP	DUCTILE IRON PIPE
<del></del>	<b>~~~</b>	DEMOLITION		<b>●</b> <sup>TMH</sup>	TELEPHONE MANHOLE	FES	FLARED END SECTION
	***************************************	SAWCUT	T	T	TRANSFORMER PAD	FM	FORCE MAIN
×	—×——	SILT FENCE			TATASI STAMEN 1778		
:::::::> · · c	· ·	SILT SOCK / STRAW WATTLE	-0-	•	UTILITY POLE	F&G	FRAME AND GRATE
	<b>—</b>	TURBIDITY CURTAIN	0-	•-	GUY POLE	F&C	FRAME AND COVER
			Ϊ	Ϊ	GUY WIRE & ANCHOR	GI	GUTTER INLET
4	— 4 <del>——</del>	MINOR CONTOUR	HH ⊡	HH ©	HAND HOLE	GT	GREASE TRAP
	<b>—</b> 20 <b>——</b>	MAJOR CONTOUR	PB ⊡	PB ⊡	PULL BOX	HDPE	HIGH DENSITY POLYETHYLENE
DYL	DYL	DOUBLE YELLOW LINE	Mato	<b>hline</b>	MATCHINE	НН	HANDHOLE
SL	SL	STOP LINE			MATCHLINE	HW	HEADWALL
						HYD	HYDRANT
		CROSSWALK					
2	<u> </u>	ACCESSIBLE CURB RAMP				INV	INVERT ELEVATION
<u>E</u> .	گِر پ	ACCESSIBLE PARKING				I=	INVERT ELEVATION
VAN	VAN	VAN-ACCESSIBLE PARKING				LP	LIGHT POLE
						MES	METAL END SECTION
						PWW	PAVED WATER WAY
						PVC	POLYVINYLCHLORIDE PIPE
						PIV	POST INDICATOR VALVE
						rı v	LUGI INDICATUR VALVE

# Description of Work

- 1. THE GOALS OF THIS PROJECT ARE TO: REMOVE THE GREAT DAM AND STABILIZE THE RIVER BED IN A WAY THAT PROTECTS THE ADJACENT PROPERTIES WHILE CREATING UPSTREAM PASSAGE FOR DIADROMOUS FISH SPECIES SUCH AS AMERICAN SHAD.
- 2. THE GREAT DAM IS A CONCRETE DAM WITH AN OGEE STYLE SPILLWAY, A FISH LADDER, A LOW-LEVEL OUTLET, AND A PENSTOCK WITH ITS ASSOCIATED HEADWORKS. THE DAM IS APPROXIMATELY 136 FEET LONG BY APPROXIMATELY 16 FEET HIGH MEASURED FROM THE TOP OF ITS TALLEST ABUTMENT TO THE STREAMBED AT ITS DOWNSTREAM FACE.
- 3. THE WORK CONSISTS OF COMPLETE REMOVAL OF THE DAM STRUCTURE INCLUDING ALL CONCRETE, METAL, STONE AND WOOD COMPONENTS. THE APPROXIMATE LIMITS AND EXTENT OF DAM REMOVAL ARE DEPICTED ON PLAN SHEETS C-2 AND C-5. BECAUSE REMOVAL OF THE DAM COULD RESULT IN AN UNSTABLE RIVERBED WITH EXCESSIVE VERTICAL DROPS INHIBITING OR PREVENTING FISH PASSAGE, UP TO APPROXIMATELY 250 LINEAR FEET OF THE RIVER CHANNEL WILL BE RE-GRADED AND STABILIZED WITH PLACED RIP RAP. PLACED RIP RAP WILL FUNCTION TO STABILIZE THE RIVERBED, PROTECT STREAMBANKS, AND LIMIT THE VERTICAL DROP ALONG THE RIVERBED. SEE SHEET C-6 FOR PROPOSED LOCATION GRADING AND LIMITS OF PLACED RIP RAP.
- . EQUIPMENT SHALL BE STAGED ALONG A FENCED OFF PORTION OF PLEASANT STREET AND ON THE EAST BANK OF THE RIVER IN FOUNDERS PARK WHERE EQUIPMENT WILL ENTER THE STREAM.
- REGRADE A PORTION OF THE EAST BANK TO ALLOW EQUIPMENT ACCESS, AND A WOODEN TIMBER BRIDGE (OR APPROVED EQUAL) WILL NEED TO BE INSTALLED TO PROVIDE ACCESS TO THE DAM. THE CONTRACTOR MAY POTENTIALLY USE THE PROPERTY OWNED BY PETER OLNEY AT 23 WATER STREET TO ACCESS THE RIVER.
- REMOVE ALL CONCRETE FROM THE RIVER, AND HAUL FOR DISPOSAL TO AN APPROVED DISPOSAL FACILITY. COMPLETELY REMOVE THE TIMBER ACCESS BRIDGE (OR APPROVED EQUAL) AND HAUL FOR DISPOSAL TO AN APPROVED DISPOSAL FACILITY.
- THE PROJECT IS IN A FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) ZONE AE, SPECIAL FLOOD HAZARD AREA, WHICH IS DEFINED AS AN AREA SUBJECT TO INUNDATION BY THE 1-PERCENT-ANNUAL-CHANCE (100-YEAR) FLOOD EVENT DETERMINED BY DETAILED METHODS. ADDITIONALLY, MUCH OF THE WORK IS LOCATED WITHIN A REGULATORY FLOODWAY AS DETERMINED BY FEMA. A REGULATORY FLOODWAY MEANS THE CHANNEL OF A RIVER OR WATERCOURSE AND THE ADJACENT LAND AREAS THAT MUST BE RESERVED IN ORDER TO DISCHARGE THE BASE FLOOD WITHOUT CUMULATIVELY INCREASING THE WATER SURFACE ELEVATION MORE THAN A DESIGNATED HEIGHT.

#### General

- 1. NOTIFY "DIG-SAFE" (1-888-344-7233) AT LEAST 72 HOURS BEFORE EXCAVATING.
- 2. ENSURE SITE SECURITY AND JOB SAFETY. CONSTRUCTION ACTIVITIES SHALL BE IN ACCORDANCE WITH OSHA STANDARDS AND LOCAL REQUIREMENTS.
- 3. APPLY SIX (6) INCHES OF LOAD AND SEED (UNLESS OTHERWISE NOTED) TO ANY UPLAND AREAS DISTURBED DURING CONSTRUCTION AND NOT RESTORED WITH IMPERVIOUS SURFACES (PAVEMENTS, WALKS, ETC.)
- 4. PERFORM ALL WORK IN STRICT COMPLIANCE WITH NH WETLANDS PERMIT, US ARMY CORPS OF ENGINEERS PERMIT, AND ALL OTHER APPLICABLE PERMITS AND REGULATIONS. THE CONTRACTOR SHALL HAVE A COPY OF ALL NECESSARY PERMITS AVAILABLE ON SITE AT ALL TIMES.
- 5. UPON AWARD OF CONTRACT, MAKE NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN NECESSARY PERMITS, PAY FEES, AND POST BONDS ASSOCIATED WITH THE WORK INDICATED ON THE DRAWINGS, IN THE SPECIFICATIONS AND IN THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL NOT CLOSE OR OBSTRUCT ROADWAYS, SIDEWALKS, AND FIRE HYDRANTS, WITHOUT APPROPRIATE PERMITS.
- 6. RESTORE AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
- 7. IN THE EVENT THAT SUSPECTED CONTAMINATED SOIL, GROUNDWATER, OR OTHER MEDIA ARE ENCOUNTERED DURING EXCAVATION AND CONSTRUCTION ACTIVITIES BASED ON VISUAL, OLFACTORY, OR OTHER EVIDENCE, STOP WORK IN THE VICINITY OF THE SUSPECT MATERIAL TO AVOID FURTHER SPREADING OF THE MATERIAL, AND NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE APPROPRIATE TESTING AND SUBSEQUENT ACTION CAN BE TAKEN.
- 8. PREVENT DUST, SEDIMENT, AND DEBRIS FROM EXITING THE SITE AND SHALL BE RESPONSIBLE FOR CLEANUP, REPAIRS AND CORRECTIVE ACTION IF SUCH OCCURS.
- 9. DAMAGE RESULTING FROM CONSTRUCTION LOADS SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR OWN EXPENSE.
- 10. CONTROL STORMWATER RUNOFF DURING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF SITE AREAS, AND SREPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO THE TOWN OF EXETER OR ADJACENT PROPERTY OWNERS. DAMAGE RESULTING FROM STORMWATER RUNOFF SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR OWN EXPENSE.
- 11. FOR PURPOSES OF THIS PLAN SET AND CONSTRUCTION SPECIFICATIONS, THE TERMS "ENGINEER" AND "MONITOR" SHALL BE SYNONYMOUS AND SHALL MEAN THE INDIVIDUAL OR FIRM RETAINED BY TOWN OF EXETER TO CONDUCT CONSTRUCTION MONITORING

#### Layout and Materials

- 1. ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE SET OR RESET BY A LICENSED LAND SURVEYOR (LLS).
- 2. IN ORDER TO PROVIDE VISUAL CLARITY ON THE PLANS, NOT ALL DEPICTED ITEMS ARE DRAWN TO THEIR ACTUAL DIMENSIONS. REFER TO THE LABELED DIMENSIONS AND THE PROVIDED DETAILS FOR ACTUAL DESIGN INFORMATION.

#### Utilities

- 1. THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE TOWN OF EXETER HAS NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS SHOWN ON THE PLANS. THE UTILITY INFORMATION SHOWN DOES NOT GUARANTEE THE ACTUAL EXISTENCE, SERVICEABILITY, OR OTHER DATA CONCERNING THE UTILITIES, NOR DOES IT GUARANTEE AGAINST THE POSSIBILITY THAT ADDITIONAL UTILITIES MAY BE PRESENT THAT ARE NOT SHOWN ON THE PLANS. PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY THAT THERE ARE NO INTERFERENCES WITH EXISTING UTILITIES INCLUDING ROUTES WITHIN THE PUBLIC RIGHTS OF WAY.
- 2. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, OR EXISTING CONDITIONS DIFFER FROM THOSE SHOWN, SUCH THAT THE WORK CANNOT BE COMPLETED AS INTENDED, THE LOCATION, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED IN WRITING TO THE ENGINEER FOR THE RESOLUTION OF THE CONFLICT. CONTRACTOR'S FAILURE TO NOTIFY PRIOR TO PERFORMING ADDITIONAL WORK RELEASES THE TOWN OF EXETER AND OTHER PROJECT PARTNERS FROM OBLIGATIONS FOR ADDITIONAL PAYMENTS WHICH OTHERWISE MAY BE WARRANTED TO RESOLVE THE CONFLICT.
- 3. NOTIFY ALL CORPORATIONS, COMPANIES, INDIVIDUALS, OR LOCAL AUTHORITIES OWNING OR HAVING JURISDICTION OVER UTILITIES RUNNING TO, THROUGH, OR ACROSS AREAS TO BE AFFECTED BY CONSTRUCTION ACTIVITIES.
- 4. LOCATE AND IDENTIFY EXISTING UTILITIES THAT ARE TO REMAIN AND PROTECT THEM FROM DAMAGE.

#### **Existing Conditions Information**

RIM ELEVATION

SEWER MANHOLE

UNDERGROUND

UTILITY POLE

REINFORCED CONCRETE PIPE

TAPPING SLEEVE, VALVE AND BOX

RCP

- 1. BASE PLAN: SEE EXISTING CONDITIONS PLANS, SHEET C-2 AND SHEET C-3.
- A. THE PROPERTY LINES SHOWN HEREON ARE BASED ON DEEDS AND PLANS OF RECORD AND THE TOWN OF EXETER GIS AND ARE NOT THE RESULT OF A BOUNDARY SURVEY BY VHB.
- B. THE EXISTING CONDITIONS SHOWN HEREON ARE BASED ON SURVEYS BY OTHERS, TOWN OF EXETER GIS AND SUPPLEMENTED BY AN ON-THE-GROUND INSTRUMENT SURVEY BY VHB, INC. BETWEEN JULY & AUGUST 2011.
- C. THE EXISTING CONDITIONS TOPOGRAPHY DEPICTED AT THE PROPERTY AT 23 WATER STREET WAS TAKEN FROM THE COASTAL LIDAR DATA SET (ACQUIRED WINTER 2010/SPRING 2011) OBTAINED FROM NH GRANIT (NEW HAMPSHIRE STATEWIDE GEOGRAPHIC INFORMATION SYSTEM (GIS) CLEARINGHOUSE) AND NOT FROM ON THE GROUND SURVEY.
- D. THE BATHYMETRY NORTHWEST OF THE GREAT DAM IS BASED ON AN ON-THE-GROUND SURVEY BY VHB, INC. BETWEEN JULY AND AUGUST 2011.
- E. THE BATHYMETRY SOUTHEAST OF THE GREAT DAM IS BASED ON AN ON-THE-GROUND SURVEY BY VHB, INC. IN SEPTEMBER 2014.
- F. THE HORIZONTAL DATUM IS BASED ON NH GRID. THE ELEVATIONS SHOWN HEREON REFER TO NAVD 1988 GEOID 12A.
- G. WETLAND BOUNDARIES DEPICTED ON PLANS ARE COWARDIN CLASSIFICATIONS COMPLETED BY A VHB WETLAND SCIENTIST USING AERIAL ORTHOIMAGERY AND NOT ON-THE-GROUND SURVEY.
- 2. GEOTECHNICAL DATA INCLUDING TEST PIT AND BORING LOCATIONS AND ELEVATIONS WERE OBTAINED FROM PARE CORPORATION AND ARE DETAILED IN THEIR REPORT TITLED "GEOTECHNICAL DESIGN BASIS REPORT, PROPOSED REMOVAL OF GREAT DAM, EXETER RIVER, EXETER, NEW HAMPSHIRE", DATED DECEMBER 2014. BORING LOCATIONS ARE DEPICTED ON SHEET C-2. BORING LOG DATA IS PROVIDED IN THE FINAL REPORT AND CAN BE OBTAINED BY CONTACTING THE TOWN OF EXETER ENGINEER, MR. PAUL VLASICH AT 603-773-6160.

#### **Notes:**

Demolition

- 1. SUBMIT THE FOLLOWING INFORMATION TO THE ENGINEER FOR REVIEW BEFORE COMMENCING WORK:
- 1.1. PERMITS FOR TRANSPORT AND DISPOSAL OF DEBRIS.1.2. DEMOLITION PROCEDURES AND OPERATIONAL SEQUENCE.
- 1.3. CALCULATIONS
- 2. DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND STATUTES.
- 3. THE DEMOLITION LIMITS DEPICTED ON THE PLANS ARE INTENDED TO AID THE CONTRACTOR DURING THE BIDDING AND CONSTRUCTION PROCESS AND IS NOT INTENDED TO DEPICT EACH AND EVERY ELEMENT OF DEMOLITION. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING THE DETAILED SCOPE OF DEMOLITION BEFORE SUBMITTING ITS BID/PROPOSAL TO PERFORM THE WORK AND SHALL MAKE NO CLAIMS AND SEEK NO ADDITIONAL COMPENSATION FOR CHANGED CONDITIONS OR UNFORESEEN OR LATENT SITE CONDITIONS RELATED TO ANY CONDITIONS DISCOVERED DURING EXECUTION OF THE WORK.
- 4. UNLESS OTHERWISE SPECIFICALLY PROVIDED ON THE PLANS OR IN THE SPECIFICATIONS, THE ENGINEER HAS NOT PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF HAZARDOUS MATERIALS, TOXIC WASTES OR POLLUTANTS AT THE PROJECT SITE. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY CLAIMS OF LOSS, DAMAGE, EXPENSE, DELAY, INJURY OR DEATH ARISING FROM THE PRESENCE OF HAZARDOUS MATERIAL AND CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE ENGINEER FROM ANY CLAIMS MADE IN CONNECTION THEREWITH. MOREOVER, THE ENGINEER SHALL HAVE NO ADMINISTRATIVE OBLIGATIONS OF ANY TYPE WITH REGARD TO ANY CONTRACTOR AMENDMENT INVOLVING THE ISSUES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF ASBESTOS OR OTHER HAZARDOUS MATERIALS.
- 5. CEASE OPERATIONS IMMEDIATELY IF ANY DAMAGE, SETTLEMENT, OR OTHER ADVERSE EFFECT ON ADJACENT STRUCTURES OCCUR. HOWEVER, IF AN UNSAFE CONDITION IS CREATED THAT WOULD POTENTIALLY CAUSE INJURY TO PERSONS OR UNDUE HARM TO PROPERTIES, TAKE WHATEVER MEASURES ARE WARRANTED TO PREVENT SUCH INJURY OR HARM. IMMEDIATELY NOTIFY THE ENGINEER AND REGULATORY AGENCIES. DO NOT RESUME OPERATIONS UNTIL CONDITIONS ARE CORRECTED, DAMAGE REPAIRED, AND APPROVAL HAS BEEN RECEIVED FROM THE APPROPRIATE AUTHORITIES AND THE OWNER'S REPRESENTATIVE.
- 6. OBTAIN WRITTEN PERMISSION FROM ADJACENT PROPERTY OWNERS WHEN DEMOLITION EQUIPMENT WILL TRANSVERSE, INFRINGE UPON, OR AFFECT ACCESS TO THEIR PROPERTY. COPIES OF THE PERMISSION DOCUMENTS SHALL BE SUBMITTED TO THE ENGINEER.
- 7. PROVIDE HOSES AND WATER CONNECTIONS AND SPRAY WATER ON DEMOLITION DEBRIS TO MINIMIZE DUST.
- 8. CLEAN ADJACENT STRUCTURES AND IMPROVEMENTS OF DUST, DIRT, AND DEBRIS CAUSED BY DEMOLITION OPERATIONS. RETURN ADJACENT AREAS TO THE CONDITION WHICH EXISTED PRIOR TO START OF WORK.
- 9. ALL HAZARDOUS WASTE REMOVAL SHALL BE PERFORMED BY A HAZARDOUS WASTER CONTRACTOR QUALIFIED AND DULY LICENSED IN THE STATE OF NEW HAMPSHIRE TO REMOVE, TRANSPORT, AND DISPOSE OF EACH TYPE OF HAZARDOUS SUBSTANCE.

#### **Erosion Control**

- 1. INSPECT AND MAINTAIN EROSION CONTROL MEASURES WITHIN TWELVE HOURS AFTER EACH STORM EVENT (0.25" OF RAINFALL OR GREATER) AND DISPOSE OF DEPOSITED SEDIMENTS IN AN UPLAND AREA SUCH THAT THEY DO NOT ENCUMBER OTHER DRAINAGE STRUCTURES, EROSION CONTROL MEASURES AND PROTECTED AREAS.
- 2. CONTROL CONSTRUCTION SUCH THAT SEDIMENTATION DOES NOT AFFECT REGULATORY PROTECTED AREAS, WHETHER SUCH SEDIMENTATION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT.
- 3. PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF TIME BEFORE THEY ARE COVERED, SEEDED, OR OTHERWISE STABILIZED TO PREVENT EROSION.
- UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER, REMOVE AND DISPOSE OF EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS.
   TEMPORARILY SEED AND MULCH AREAS REMAINING UNSTABILIZED FOR A PERIOD OF MORE THAN 7 DAYS. CLEAN, WEED
- FREE, STRAW MULCH SHALL BE APPLIED AT A MINIMUM RATE OF 1-1/2 TONS/ACRE, WHICH EQUALS A THICKNESS OF APPROXIMATELY 1 INCH.
- 6. PERMANENT SEEDING SHALL OCCUR BETWEEN APRIL 1 AND JUNE 1, AND/OR BETWEEN AUGUST 15 AND OCTOBER 15. ALL SEEDING SHALL BE STRAW MULCHED.
- 7. APPLY WATER AS NEEDED TO CONTROL DUST
- 8. TEMPORARILY SEED AND MULCH SOILS TO BE STOCKPILED FOR A PERIOD OF MORE THAN 7 DAYS. INSTALL SILT FENCING ALONG DOWNHILL SIDE OF STOCKPILES.
- 9. PROVIDE NECESSARY EROSION CONTROL MEASURES TO INSURE THAT SURFACE WATER RUNOFF FROM UNSTABILIZED AREAS DOES NOT CARRY SILT, SEDIMENT, AND OTHER DEBRIS OUTSIDE OF THE LIMITS OF WORK.
- 10. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:
- A. MINIMUM OF 85% VEGETATED COVER HAS BEEN ESTABLISHED;
   B. A MINIMUM OF 3-IN OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIPRAP, HAS BEEN INSTALLED;
   C. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED. THE ENGINEER SHALL BE RESPONSIBLE FOR MAKING A DETERMINATION AS TO WHETHER AN AREA IS STABLE.
- 11. ALL DITCHES, SWALES, AND DRAINAGE BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- 12. LOAM, SEED, MULCH, OR MAT FILL ALL CUT AND FILL SLOPES, IF REQUIRED, WITHIN 72 HOURS OF ACHIEVING FINISHED
- 13. ALL PERMANENT AND TEMPORARY SEEDING SHALL BE FREE OF NOXIOUS WEED SEED.
- 14. NO FERTILIZERS (EXCEPT LIMESTONE) SHALL BE USED WITHIN 25 FEET OF THE RIVER. FROM 25–250 FEET, LOW PHOSPHATE, SLOW RELEASE NITROGEN FERTILIZER MAY BE USED. THESE FERTILIZERS MUST BE GUARANTEED ON THE PACKAGE LABEL TO CONTAIN NOT MORE THAN 2 PERCENT PHOSPHOROUS AND AT LEAST 50 PERCENT SLOW RELEASE NITROGEN.
- 15. INSTALL STABILIZED CONSTRUCTION ENTRANCES AT CONSTRUCTION ENTRANCES. DETERMINE FINAL LOCATION PRIOR TO CONSTRUCTION.

#### Winter Construction

- 1. ALTHOUGH WINTER CONSTRUCTION IS NOT ANTICIPATED, STABILIZE ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH. STABILIZATION METHODS INCLUDE SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE AND SECURED WITH ANCHORED NETTING, ELSEWHERE. COMPLETE THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING IN ADVANCE OF THAW OR SPRING MELTS, DO NOT INSTALL OVER ACCUMULATED SNOW OR FROZEN GROUND.
- 2. TEMPORARILY STABILIZE ALL DITCHES OR SWALES, WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS, WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH,

#### State Regulations

- 1. RSA 482-A, WETLAND DREDGE AND FILL, NH DEPARTMENT OF ENVIRONMENTAL SERVICES, WETLANDS BUREAU.
- CLEAN WATER ACT, SECTION 401 WATER QUALITY CERTIFICATION, NH DEPARTMENT OF ENVIRONMENTAL SERVICES, WATERSHED MANAGEMENT BUREAU.
- 3. RSA 483-B, COMPREHENSIVE SHORELAND PROTECTION ACT, NH DEPARTMENT OF ENVIRONMENTAL SERVICES, WETLAND


## Federal Regulations

- 1. CLEAN WATER ACT, SECTION 404, WETLAND DREDGE AND FILL PERMIT, US ARMY CORPS OF ENGINEERS.
- 2. USFWS ENDANGERED SPECIES ACT AND BIOLOGICAL OPINION.
- NATIONAL HISTORIC PRESERVATION ACT, SECTION 106 CONSULTATION, NH STATE HISTORIC PRESERVATION OFFICE (NH DIVISION OF HISTORICAL RESOURCES).

Engineers Scientists Planners Designers

f 617.924.2286





Great Dam Removal and

**Exeter River Restoration** 

Exeter, New Hampshire

Exeter, New Hampsin

Permitting

Not Approved for Construction

Drawing Ti

Legend and General Notes

Drawing Number



Project Number 52151.04

LD-LG.DWG

Engineers Scientists Planners Designers



n. Revision Date Appvd.

No. Revision Date Appvd.

Designed by TM Drawn by JB Checked by JSACAD checked by TM Approved by JSAScale 1''=20' Date 12/07/15Project Title

Great Dam Removal and Exeter River Restoration

Exeter, New Hampshire

Permitting

Not Approved for Construction

wing Title


**Existing Conditions Plan** 

Drawing Number


C-2

2 of 14


Project Number 52151.04
















Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Permitting

Not Approved for Construction


**Existing Conditions Plan** 

LD-PRG.DWG

VERTICAL SCALE IN FEET

1+20

VERTICAL SCALE IN FEET



#### Pre-Construction

- 1. TWO WEEKS PRIOR TO CONSTRUCTION, A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD WITH THE CONTRACTOR, TOWN, ENGINEER, AND REGULATORY AGENCIES TO DISCUSS THE PROPOSED PLAN/SCHEDULE, REVIEW PERMIT CONDITIONS, AND TO DISCUSS HIGH-FLOW CONTINGENCY PLANS.
- 2. PROVIDE A FINAL CONSTRUCTION SCHEDULE AND METHODS TO ENGINEER, TOWN AND NHDES AT LEAST TWO WEEKS PRIOR TO CONSTRUCTION. DOCUMENT DETAILS OF PROPOSED RIVER DIVERSION, COFFERDAM CONSTRUCTION, CONSTRUCTION PHASING AND TEMPORARY EROSION CONTROL MEASURES TO BE IMPLEMENTED. ADDRESS THE ENTIRE WATER MANAGEMENT AND CONTROL PLAN, DAM REMOVAL AND RIVER RESTORATION PORTIONS OF THE PROJECT.

#### Timing

1. IN-STREAM WORK FOR DAM REMOVAL SHALL NOT COMMENCE UNTIL DRY WEATHER IS FORECASTED, GENERALLY FOR AT LEAST 3 TO 4 DAYS. SHOULD A SIGNIFICANT (GREATER THAN 0.5 INCH) RAINFALL EVENT OCCUR WHILE WORK IS BEING CONDUCTED IN THE RIVER, REMOVE ALL EQUIPMENT FROM THE RIVER UNTIL THE HIGH RIVER FLOW SUBSIDES.

#### Construction Staging & Initial Draw Down

1. INSTALL TEMPORARY EROSION CONTROL MEASURES PRIOR TO CONSTRUCTION. EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL THE DISTURBED AREA IS STABILIZED.

- 2. STRIP LOAM WITHIN AREAS DISTURBED BY GRADING AND/OR EQUIPMENT ACCESS AND STOCKPILE FOR LATER RESTORATION. DO NOT SALVAGE TOPSOIL FROM AREAS WITH NON-NATIVE, INVASIVE SPECIES.
- 3. GRADE THE EASTERN BANK AT THE CAUSEWAY TO ALLOW FOR EQUIPMENT ACCESS. DRAW DOWN THE IMPOUNDMENT BY OPENING THE LOW LEVEL OUTLET ON THE EAST BANK.

(OUTSIDE OF THE TEMPORARY COFFERDAM).

Phase 1 - Suggested Sequence of Construction

SHOWN (APPROX BANKFULL STORM ELEVATION)

4. REMOVE LOWER FISH WEIR IN WEST SIDE OF RIVER

6. REMOVE CONCRETE DAM IN WEST SIDE OF RIVER

8. SEED AND RESTORE WESTERN BANKS AS SHOWN ON SHEET C-10.

7. GRADE CHANNEL WITHIN COFFER DAM AREA

2. INSTALL COFFER DAM (SAND BAGS, PORTADAM, OR APPROVED EQUAL) TO ALLOW WORK ON

WEST SIDE OF CHANNEL. COFFER DAM HEIGHT TO TRANSITION BETWEEN ELEVATIONS

3. INSTALL TIMBER MATS & RAMP ACCESS BRIDGE FROM EAST BANK TOWARDS WEST BANK


1. DRAW DOWN IMPOUNDMENT

REMOVE FISH LADDER

- CONDUCT WORK IN THE DRY TO THE EXTENT POSSIBLE TO MINIMIZE TURBIDITY. ADDRESS WET VS. DRY CONSTRUCTION IN THE FINAL SCHEDULE & METHODS. METHODS TO BE REVIEWED AND ACCEPTED BY THE ENGINEER AND NHDES.
- 6. INSTALL A TEMPORARY COFFERDAM ON THE UPSTREAM FACE OF THE DAM TO ALLOW FOR ADEQUATE DE-WATERING, SITE PREPARATION, AND DEMOLITION OF THE DAM. CHOOSE THE COFFERDAM CONSTRUCTION TYPE AS WELL AS METHODS FOR MANAGING AND CONTROLLING WATER THROUGHOUT THE CONSTRUCTION PERIOD, BUT THE DESIGN IS SUBJECT TO REVIEW AND ACCEPTANCE BY THE ENGINEER AND NHDES WETLANDS BUREAU.
- INSTALL TIMBER ACCESS BRIDGE FROM EAST BANK TO WEST BANK. PLACE THE COFFERDAM, STARTING FROM THE WEST BANK TO BEGIN DEMOLITION OF DAM ALONG WEST BANK MOVING TOWARD THE EAST ABUTMENT. THE COFFERDAM SHOULD EXTEND FAR ENOUGH DOWNSTREAM TO PREVENT BACKWATER FROM ENTERING THE DAM

REMOVAL AREA.

DEWATER TURBID WATER, IF REQUIRED, BY DISCHARGING TO A STABILIZED SEDIMENT BASIN/TRAP CONSTRUCTED IN ONSITE UPLANDS AND IN ACCORDANCE WITH THE "STORMWATER MANAGEMENT AND EROSION AND SEDIMENT CONTROL HANDBOOK FOR DEVELOPING AREAS IN NEW HAMPSHIRE." LOCATE BASIN/TRAP IN AN UPLAND AREA AS FAR AS PRACTICAL FROM THE RIVER. CLEAN WATER MAY BE DISCHARGED DIRECTLY.




PHASE 2

- TO TRANSITION BETWEEN ELEVATIONS SHOWN (APPROX BANKFULL ELEVATION)
- 2. ADJUST TIMBER MATS IF NECESSARY
- 3. REMOVE FISH WEIR IN EAST SIDE OF RIVER
- 4. REMOVE CONCRETE DAM IN EAST SIDE OF RIVER
- 5. SAWCUT CONC. AT DAM HEADWORKS AND REMOVE GEAR WORKS FOR FUTURE USE
- 6. SEAL PENSTOCK AND REMOVE LOW FLOW OUTLET
- 7. GRADE REMAINING CHANNEL WITHIN COFFER DAM AREA
- 8. SEED AND RESTORE EASTERN BANKS AS SHOWN ON SHEET C-10.

#### Phase 3 - Suggested Sequence of Construction

1. FOLLOWING FIRST SPRING MIGRATION SEASON POST CONSTRUCTION, ADJUST GRADING AND BOULDER PLACEMENT AT DIRECTION OF ENGINEER



**Scientists** 

Designers

617.924.1770 f 617.924.2286

Great Dam Removal and **Exeter River Restoration** 

Date 12/07/15


Exeter, New Hampshire

Permitting

Scale 1"=30'

Not Approved for Construction

Staging and Construction Sequence



Engineers Scientists

Planners Designers

Watertown, MA 02471

617.924.1770

f 617.924.2286

Scale 1"=20' Date 12/07/15


Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Permitting

Not Approved for Construction

Structure Demolition Plan




Engineers Scientists Planners

Designers

VID Walnut Street

PO Box 9151 Watertown, MA 02471 617.924.1770 f 617.924.2286



Great Dam Removal and Exeter River Restoration

Exeter, New Hampshire

Permitting

Not Approved for Construction

ving Title


River Channel Grading Plan

Drawing Number

C-6


et of 6 14

Project Number 52151.04



# **Granite Buttress at Green Bean on Water (STA 1+25)**


N.T.S.



# **Typical Riffle Section (STA 2+00)** PLANTED BANKFULL BENCH PLANTED BANKFULL BENCH COBBLE CHANNEL BANKFULL FLOW WSE APRIL-JUNE 95% FLOW WSE APRIL-JUNE 5% FLOW WSE EXISTING CHANNEL BOTTOM 12" TOPSOIL SEEDED WITH WETLAND MIX COBBLE-BOULDER MIX TO BEDROCK, 30-IN (MIN.) APPROXIMATE BEDROCK BOULDER CLUSTER COBBLE-BOULDER MIX TO 6 FT BOTTOM WIDTH BEDROCK, 30-IN (MIN.)

# Typical Pool Section (STA 2+50)

N.T.S.



Typical Section at Outfall along Pleasant Street (STA 3+08)



Designed by TM Drawn by JB

Exeter, New Hampshire

Permitting

Typical

**Cross Sections** 

Date 12/07/15

Great Dam Removal and

**Exeter River Restoration** 


Not Approved for Construction


Scale NTS

Sheet of 8 14

Project Number 52151.04










**Engineers** Scientists **Planners** Designers PO Box 9151 Watertown, MA 02471 617.924.1770 f 617.924.2286

FRANKLIN ST. DRY HYDRANT PLAN












PUMP HOUSE PROFILE



Great Dam Removal and **Exeter River Restoration** 

Exeter, New Hampshire

Permitting

Not Approved for Construction

Conceptual Intake Designs

Designed by TM Drawn by JB

Engineers Scientists

Planners

Designers

Watertown, MA 02471

617.924.1770 f 617.924.2286

Scale 1"=20' Date 12/07/15 Great Dam Removal and

**Exeter River Restoration** 

Exeter, New Hampshire


Permitting

Not Approved for Construction


Restoration and Planting Plan

C-10

Project Number 52151.04







Great Dam Removal and **Exeter River Restoration** 


Exeter, New Hampshire

Permitting


Not Approved for Construction

Wetland Impact Plan

Sheet of 11 14



FRANKLIN ST. DRY HYDRANT PLAN



# PUMP HOUSE PLAN

Legend					
OHW	ORDINARY HIGH WATER				
——— ТОВ ————	TOP OF BANK				
А	WETLAND IMPACT LOCATION				
	N.H. WETLANDS BUREAU AND U.S. ARMY CORPS WETLAND IMPACT - PERMANENT				
	N.H. WETLANDS BUREAU AND U.S. ARMY CORPS WETLAND IMPACT - TEMPORARY				
+ + + + + + + + + + + + + + + + + + + +	TEMPORARY SHORELAND IMPACT				

Wetland Classification Codes

R2UBH(h) RIVERINE, LOWER PERENNIAL, UNCONSOLIDATED BOTTOM,

PERMANENTLY FLOODED, IMPOUNDED.


R2UBH(h) RIVERINE, LOWER PERENNIAL, EMERGENT, PERMANENTLY

FLOODED, IMPOUNDED.

Dry Hydrant & Municipal Water Intake Wetland Impact Summary							
	Area (sf)						
Wetland Classification	Impact Permanent Location Impacts		Temporary Impacts		Purpose		
		Bed	Bank	Bed	Bank		
R2UBH(h)	Α			620		COFFERDAM	
R2UBH(h)	В	1,220	80			PIPE INSTALLATION	
R2UBH(h)	С			330	20	COFFERDAM	
R2UBH(h)	D	820	150			PIPE INSTALLATION	
TOTAL		2,040	230	950	20		

#### RSA 482-A IMPACTS

	3 2/10 S
TEMPORARY IMPACTS:	970 S
PERMANENT IMPACTS:	2,270 S



Engineers Scientists Planners

Designers

PO Box 9151 Watertown, MA 02471 617.924.1770 f 617.924.2286

Great Dam Removal and Exeter River Restoration

Exeter, New Hampshire

Issued for Permitting

Not Approved for Construction

Drawing T

Wetland Impact Plan

Drawing Number

**C-**12


Project Number 52151.04


#### Notes:

- 1. STRAW WATTLE SHALL BE AS MANUFACTURED BY EARTHSAVER OR APPROVED EQUAL.
- 2. STRAW WATTLES SHALL OVERLAP A MINIMUM OF 12 INCHES.
- 3. STRAW WATTLE SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM EVENTS, AND REPAIR OR REPLACEMENT SHALL BE PERFORMED PROMPTLY AS NEEDED.
- 4. TEMPORARY STRAW WATTLES TO BE REMOVED BY CONTRACTOR. ALL OTHERS TO REMAIN IN PLACE UNLESS DIRECTED OTHERWISE BY ENGINEER.
- 5. IF NON BIODEGRADABLE NETTING IS USED THE NETTING SHALL BE COLLECTED AND DISPOSED OF OFFSITE.

#### Silt Fence/Sock - Erosion Control Barrier

N.T.S.







#### Notes:

- INSTALL SILTSACK IN ALL CATCH BASINS WITHIN LIMIT OF WORK BEFORE COMMENCING WORK OR IN PAVED AREAS AFTER BINDER COURSE IS PLACED AND HAY BALES HAVE BEEN REMOVED
   GRATE TO BE PLACED OVER SILTSACK.
- 3. SILTSACK SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM EVENTS AND CLEANING OR REPLACEMENT SHALL BE PERFORMED PROMPTLY AS NEEDED. MAINTAIN UNTIL UPSTREAM AREAS HAVE BEEN PERMANENTLY STABILIZED

#### Siltsack Sediment Trap

N.T.S.






#### **Cross-section**

**Notes:** 

- 1. ENTRANCE WIDTH SHALL BE A TWENTY (20) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
- 2. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS—OF—WAY MUST BE REMOVED IMMEDIATELY. BERM SHALL BE PERMITTED. PERIODIC INSPECTION AND MAINTENANCE SHALL BE PROVIDED AS NEEDED.
- 3. STABILIZED CONSTRUCTION EXIT SHALL BE REMOVED PRIOR TO FINAL FINISH MATERIALS BEING INSTALLED.
- 4. FINAL LOCATIONS OF STABILIZED CONSTRUCTION EXIT TO BE CONFORMED WITH ENGINEER PRIOR TO CONSTRUCTION.

#### **Stabilized Construction Exit**

N.T.S.




1.CONTRACTOR TO DESIGN AND INSTALL COFFER DAM TO CONTROL OVERTOPPING FLOWS AND PREVENT EROSION OR DAMAGE TO SURROUNDING LAND

**Notes:** 

#### Coffer Dam (Sand Bags)


N.T.S.



2. HYDRANTS AND COMPONENTS SHALL BE CONSTRUCTED IN ACCORDANCE

WITH LOCAL FIRE DEPARTMENT STANDARDS AND PAINTED ACCORDINGLY.


Dry Hydrant N.T.S.



- 1. SLOPE TO BE FOUNDED ON UNDISTURBED MATERIAL OR FILL THAT HAS BEEN COMPACTED. FILL SHALL CONSIST OF A MIXTURE OF FINE TO COARSE SAND.
- 2. ROCK ARMOR SHALL BE NHDOT CLASS B RIPRAP.
- 3. ROCK SHALL COMPLETELY ENCASE EXPOSED PORTIONS OF CASSION.


#### **Rock Armored Bank**

N.T.S.



#### **Turbidity Curtain**

N.T.S.



Engineers Scientists Planners

Designers

PO Box 9151

617.924.1770

f 617.924.2286

Watertown, MA 02471

Exeter, New Hampshire

Permitting

Not Approved for Construction

rawing Title

Details

Drawing Number

Project Number


C-13

of 13 14

52151.04

LD-DT.DWG





#### 7.5' HIGH x 14.0' WIDE PENSTOCK CLOSURE

N.T.S.

STONE CLASS	STONE SIZE (IN)
D95	24 - 40
D84	18 - 24
D50	10 — 15
D30	5 – 8
D16	2 - 4


#### NOTE

- 1. CONTRACTOR SHALL ADD 10% SAND TO COBBLE— BOULDER MIX.
- 2. CONTRACTOR TO PLACE MINIMUM 30 INCH DEPTH OF SPECIFIED BED MATERIAL.

# **Cobble-Boulder Bed Material Specification**


N.T.


\*\*\* MINIMUM X—Y—Z DIMENSIONS FOR ALL STRUCTURE STONES SHALL MEET THE MINIMUM SIZE REQUIREMENTS GIVEN IN THE TABLE BELOW.




## **Boulder Axis Detail**


N.T.S.





**Front Elevation View** 






**Profile Through Center of Riffle Crest** 

## **Riffle Crest Detail**

N.T.S.



PLACE BOULDERS APPROXIMATELY—

1 DIAMETER APART, GAPS

BETWEEN BOULDERS 3' — 5'.

ARRANGE BOULDERS IN CLUSTERS OF 3 TO 5 MAXIMUM SPACING BETWEEN BOULDER CLUSTERS IS 20 FEET

COBBLE-BOULDER-SAND STREAMBED LAYER


KEY BOULDER PROTRUSION
HEIGHT 12"-18"
ABOVE BED

KEY BOULDER A MIN.
OF 1-FT BELOW
BOTTOM OF
COBBLE-GRAVEL LAYER

#### **Boulder Cluster**

N.T.S.





Great Dam Removal and Exeter River Restoration

Exeter, New Hampshire

Permitting

Not Approved for Construction

Drawing T

Details (2)

Drawing Number

**C-14** 

Project Number 52151.04

LD-DT.DWG